

Sub-Subdivisions of T. 3 North, R. 34 East

Chains	<p>of earth <math>1\frac{1}{2}</math> ft. high, <math>3\frac{1}{2}</math> ft. base over it.</p>	
75.00	Top of ridge, bears S.	450
80.40	To point of beginning.	
	Land, rolling.	
	Soil, 1st rate. Partly cultivated.	
	Oct. 12, 1887.	
<hr/>		
	East on random through S. $\frac{1}{8}$ of Sec. 22.	
	Va. 20° East.	
	Commencing at 1/16 sec. cor. 20 chains N. of SW. cor. of Sec. 22, set temporary cors. at 20, 40 and 60 chains, and at	
80.30	Intersect E. bdy. 85 lks. N. of 1/16 sec. cor. Thence N. 89° 23' West on true line.	
15.20	Fence, N. and S. and enter field.	
20.07	Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, $5\frac{1}{2}$ ft. dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.	
39.80	Spring branch 2 lks. wide, NW.	
40.15	Set post 3 ft. long, 3 ins. square, 24 ins. in the ground for 1/16 sec. cor., marked 1/16 S on N. face. Dug pits 18x18x12 ins. E. and W. of stake, $5\frac{1}{2}$ ft. dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base around post.	
40.30	Cor. of door yard of dwelling of Mr. Russia.	
60.22	Set post 3 ft. long, 3 ins. square, 24 ins. in the ground, marked 1/16 S on N. face for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, $5\frac{1}{2}$ ft. dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.	
61.20	Leave field, N. and S.	
63.00	Wagon road, N. and S.	