

Sub-Subdivisions of T. 3 North, R. 34 East

Chains 80.30	To point of beginning. Land, mostly level. Soil, 1st rate.
	East on random through Center of Sec. 22 Va. 20° East.
80.20	Beginning at $\frac{1}{4}$ sec. cor. bet. Secs. 21 and 22, set temporary cors. at 20, 40 and 60 chains, and at Intersect E. bdy. 95 lks. N. of $\frac{1}{4}$ sec. cor. Thence. N. 89°19' West on true line.
20.05	Deposited a pint flask 12 ins. in the ground for $\frac{1}{16}$ sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, $5\frac{1}{2}$ ft. dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked $\frac{1}{16}$ S on N. face.
35.00	Spring branch, 2 lks. NE.
40.10	Set post 3 ft. long, 3 ins. square, 24 ins. in the ground, for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ S on N. face. Dug pits 18x18x12 ins. E. and W. of stake, $5\frac{1}{2}$ ft. dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base around post.
48.00	Enter field, SW.
60.15	Deposited charred stake 12 ins. in the ground for $\frac{1}{16}$ sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, $5\frac{1}{2}$ ft. dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked $\frac{1}{16}$ S on N. face.
80.20	To point of beginning. Land, rolling. Soil, 1st rate. Partly cultivated.
	East on random through N. $\frac{1}{2}$ of Sec. 22. Va. 20° East. Commencing at $\frac{1}{16}$ sec. cor. 20 chains N. of $\frac{1}{4}$ sec. cor. bet. Secs. 21 and 22, set temporary cors. at 20, 40