

Sub-Subdivisions of T. 3 North, R. 34 East

Chains	1/16 S on N. face.
80.20	To point of beginning.
	Land, gently rolling.
	Soil, 1st rate.
North on random through E. $\frac{1}{2}$ of Sec. 10.	
Va. $20\frac{1}{4}^{\circ}$ East.	
Commencing at 1/16 sec. cor. 20.05 chs. W. of SE. cor. of Sec. 10, set temporary cors. at 20, 40 and 60 chains, and at	
79.76	Intersect N. bdy. 10 lks. W. of 1/16 sec. cor. Thence S.4'.W. on true line.
19.94	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, $5\frac{1}{2}$ ft. dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it, and in E. pit, drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
39.88	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, $5\frac{1}{2}$ ft. dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it, and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
59.82	Deposited charred stake 12 ins. in the ground, for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, $5\frac{1}{2}$ ft. dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
79.76	To point of beginning.
	Soil good.
	Land, level.
	Oct. 13, 1887
East on random through S $\frac{1}{2}$ of Sec. 33	
Va. $20\frac{1}{2}^{\circ}$ East	