

Sub-Subdivisions of T. 3 North, R. 34 East

Chains	1/16 S on N. face.	
24.00	Canon, bears S.	-50
39.95	Deposited charred stake 12 ins. in the ground for $\frac{1}{4}$ sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, $5\frac{1}{2}$ ft. dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked $\frac{1}{4}$ S on N. face	
50.00	Canon bears S.	-75
59.92	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, $5\frac{1}{2}$ ft. dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it, and in E. pit, drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.	
79.90	To point of beginning. Land, rolling. Soil, 1st rate. Not cultivated.	
<p>East on random through N. <math>\frac{1}{2}</math> of Sec. 33. Va. 20° East.</p> <p>Beginning at 1/16 sec. cor. 20 chains N. of <math>\frac{1}{4}</math> sec. cor. bet. Secs. 32 and 33. Set temporary cors. at 20, 40 and 60 chains, and at</p>		
79.84	Intersect E. bdy. at 1/16 sec. cor. Thence West on true line	
19.96	Set basalt stone 9x8x7 ins. 6 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stone, $5\frac{1}{2}$ ft. dist., and raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it, and marked stone 1/16 on N. face.	
20.00	Small gulch, S.	-20
39.92	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, $5\frac{1}{2}$ ft. dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked	