

Sub-Subdivisions of T. 3 North, R. 34 East

Chains 79.92	<p>To point of beginning.</p> <p>Land, rolling.</p> <p>Soil, 1st rate. Not improved.</p>
<p>East on random through Center of Sec. 28.</p> <p>Va. 20° East.</p>	
80.00	<p>Commencing at $\frac{1}{4}$ sec. cor. bet. Secs. 28 and 29, set temporary cors. at 20, 40 and 60 chains, and at Intersect E. bdy. 17 lks. N. of $\frac{1}{4}$ sec. cor. Thence N.89°53' West on true line.</p>
20.00	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5$\frac{1}{2}$ ft. dist. Raised mound of earth, 1$\frac{1}{2}$ ft. high, 3$\frac{1}{2}$ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S. on N. face.</p>
40.00	<p>Deposited charred stake 12 ins. in the ground for $\frac{1}{4}$ sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5$\frac{1}{2}$ ft. dist. Raised mound of earth 1$\frac{1}{2}$ ft. high, 3$\frac{1}{2}$ ft. base over it, and in E. pit, drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked $\frac{1}{4}$ S. on N. face.</p>
60.00	<p>Deposited charred stake, 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5$\frac{1}{2}$ ft. dist. Raised mound of earth 1$\frac{1}{2}$ ft. high, 3$\frac{1}{2}$ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p>
80.00	<p>To point of beginning.</p> <p>Land, slightly rolling.</p> <p>Soil, 1st rate. Not improved.</p>
<p>East on random through N. $\frac{1}{2}$ of Sec. 28.</p> <p>Va. 20° East.</p>	
<p>Beginning at 1/16 sec. cor. 20 chains N. of $\frac{1}{4}$ sec. cor. bet. Secs. 28 and 29, set temporary cors. at 20, 40</p>	