

Sub-Subdivisions of T. 3 North, R. 34 East

Chains	and 60 chains, and at
80.08	Intersect E. bdy. 21 lks. N. of 1/16 sec. cor. Thence N.89°51' W. on true line.
20.02	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
40.04	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
60.06	Deposited charred stake, 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
80.08	To point of beginning. Land, rolling. Soil, 1st rate. Not cultivated.
East on random through S ½ of Sec. 21.	
Va. 20¼° East.	
Beginning at 1/16 sec. cor. 20 chains N. of SW. cor. of Sec. 21, set temporary cors. at 20, 40 and 60 chains, and at	
79.87	Intersect E. bdy. 10 lks. N. of 1/16 sec. cor. Thence N.89°56' W. on true line.
19.96	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. East and West. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake,