

Sub-Subdivisions of T. 3 North, R. 34 East

Chains 59.91	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. & W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit, drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
79.88	To place of beginning. Land, level. Soil, 1st rate. Not improved.
Oct. 6, 1887.	
From the ¼ section corner between Sections 20 and 29, I run N. through the Center of Sec. 20.	
Va. 20° E.	
20.00	Deposited charred stake 12 ins. in the ground for 1/16 section corner. Dug pits 18x18x12 ins. N. and S. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in North pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on W. face.
40.00	Deposited charred stake 12 ins. in the ground for ¼ sec. cor. Dug pits 18x18x12 ins. N. and S. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in N. pit drove a stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked ¼ S on W. face.
Land, level. Soil, 1st rate. Not cultivated.	
Thence I run East on a random line through Center of Sec. 20.	
Va. 20½° E.	