

Sub-Subdivisions of T. 3 North, R. 34 East

<p>Chains 74.65</p>	<p>Intersect W. bdy. Township 110 lks. S. of 1/16 sec. cor. Thence S.89°10' E. on true line.</p>
<p>14.65</p>	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit, drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p>
<p>34.65</p>	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth, 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p>
<p>54.65</p>	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p>
<p>74.65</p>	<p>To point of beginning. Land, level. Soil, 1st rate. Not cultivated.</p>
<p>West on random through Center of Sec. 31. Va. 20° East.</p>	
<p>Commencing at ¼ sec. cor. bet. Secs. 31 and 32, set temporary cors. at 20, 40 and 60 chains, and at</p>	
<p>74.70</p>	<p>Intersect W. bdy. of Township 100 lks. S. of ¼ sec. cor. Thence S.89°15' East on true line.</p>
<p>14.70</p>	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake 2 ft.</p>