

Sub-Subdivisions of T. 3 North, R. 34 East

| Chains | long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face. |
|--|---|
| 54.75 | Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face. |
| 74.75 | To point of beginning. Land, rolling. Soil, 1st rate. |
| <hr/> West on random through S. ½ of Sec. 30. Va. 20° East. | |
| 74.50 | Commencing at 1/16 sec. cor. bet. Secs. 29 and 30, 20 chains N. of SE. cor. of Sec. 30, set temporary cors. at 20, 40 and 60 chains, and at Intersect W. bdy. Township 105 links S. of 1/16 sec. cor. Thence S.89°12' East on true line. |
| 14.50 | Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and West of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face. |
| 34.50 | Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face. |
| 54.50 | Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ |