

Sub-Subdivisions of T. 3 North, R. 34 East

Chains	12 inches in the ground, marked 1/16 S on North face.
74.60	To point of beginning. Land, level. Soil, 1st rate. Not improved.
<hr/> West on random through N. $\frac{1}{2}$ of Sec. 30.	
Va. 20° East.	
Commencing at 1/16 section corner, 20 chains North of $\frac{1}{4}$ section corner between sections 29 and 30, set temporary corners at 20, 40 and 60 chains, and at	
74.60	Intersect West boundary of Township 98 links South of 1/16 section corner
Thence	
N. 89°15' East on true line.	
14.70	Set post 3 feet long, 3 inches square, 24 inches in the ground for 1/16 section corner. Marked 1/16 S on North face. Dug pits 18x18x12 inches East and West of stake, 5 $\frac{1}{2}$ feet dist., and raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ feet base over it.
34.70	Set post 3 feet long, 3 inches square, 24 inches in the ground for 1/16 section corner, marked 1/16 S on N. face. Dug pits 18x18x12 inches East and West of stake, 5 $\frac{1}{2}$ feet dist., and raised mound of earth 1 $\frac{1}{2}$ feet high, 3 $\frac{1}{2}$ feet base over it.
54.70	Set post 3 feet long, 3 inches square, 24 inches in the ground for 1/16 section corner, marked 1/16 S on North face. Dug pits 18x18x12 inches East and West of stake, 5 $\frac{1}{2}$ feet dist., and raised mound of earth 1 $\frac{1}{2}$ feet high, 3 $\frac{1}{2}$ feet base over it.