

Sub-Subdivisions of T. 3 North, R. 34 East

Chains

74.70

To point of beginning.

Land, level.

Soil, 1st rate.

Not cultivated.

Oct. 7, 1887.

Examination of Corners: Exteriors of T. 3 North, R. 34 East Willamette Meridian, Oregon, as surveyed by James P. Currin and James E. Noland, U. S. Deputy Surveyors, under their special Contract, dated May 4, 1887.

Find cor. to T. 3 & 4 N., R. 34 & 35 E. to be a pine post, 48x6x8 ins., 24 ins. in the ground, marked S 31 T 4 N R 35 E on NE., S 6 T 3 N R 35 E on SE., S 1 T 3 N R 34 E on SW., S 36 T 4 N R 34 E on NW. faces with 6 notches on N., E., S. & W. edges, with pits, 6 feet dist. on each line & earth mound around post.

South to corner Secs. 1, 6, 7 & 12, a stone 12x10x8 ins., firmly set in the ground, with 1 notch on North and 5 on South edges. Pits 5 1/2 feet dist. in each section. Mound around it. Pits partly filled. Mound scattered.

South between sections 7 and 12, I find that corner, sections 7, 12, 13 & 18 is plowed up and gone.

Going South to the corner to sections 19, 24, 13 & 18, I found a post, 4 feet long by 4 inches square, firmly set in the ground, marked S 18 T 3 N on NE., S 19 R 35 E on SE., S 24 R 34 E on SW., S 13 on NW. faces, with 3 notches on North and South edges. Mound and pits nearly destroyed by plowing.