

Exteriors of T. 3 North, R. 34 East
Examination of Corners

Chains

Corner to sections 19, 24, 25 & 30, a post, 2 feet long, 4 inches square, broken off, marked S 19 on NE., S 30 R 35 E on SE., S 25 R 34 S on SW., S 24 T 3 N on NW. faces, with 4 notches on N. and 2 on South edges, with a pit in each section, $5\frac{1}{2}$ feet dist., partly filled. Mound badly scattered. Reset post in earth mound.

South between sections 25 and 30. To corner, sections 25, 30, 31 and 36, a post, 4 feet long, 4 inches square, firmly set in the ground, marked S 30 T 3 N, NE., S 31 R 35 E on SE., S 36, SW., S 25 R 34 E on NW. faces. I cut 5 notches on North and 1 on South edges. Pits and mound defaced by plow.

Exteriors of T. 4 North, R. 34 East
Examination of Corners

Found mound and pits for corner, Secs. 2, 3, 34 & 35, all in good condition, but stone has been pulled out & is gone. No material to replace it. East on S. bdy. of Sec. 35 to cor. Secs. 35 & 36. All trace of pits, mound & post are gone. This corner stood in a garden & has been destroyed by plowing.

April 26th 1890.

Exteriors of T. 3 North, R. 34 East
Examination of Corners

Cor. to Secs. 31 & 32 on Township line, I find to be a post, 4 ft. long by 4 ins. square, marked S 32 T 3 N on NE., S 31 R 34 E on NW., & T 2 N on S. faces. No notches. I cut 5 notches on E. & one on W. edges. Earth mound & pits well preserved. S.89°46'E. on S. bdy. of Sec. 32. Passed intermediate corners, all in good condition, to cor. Secs. 32 & 33.