

Survey of the Exterior lines of Township number 3, North of the Base Line of Range 36, East of Willamette Meridian, in the State of Oregon, by William H. Odell, deputy Surveyor under his contract, No. 114, bearing date, July 2nd 1886.

Chains	North on East boundary of Section 36.	Var. 21° East.
40.00	Set post corner for $\frac{1}{4}$ section on side hill on brink of mountains, from which	A fir, 20 in dia. bears S.40°E. 21 lks.
	A fir, 10 in. dia. bears N.10°W. 50 lks.	
80.00	Set post corner for sections 25, 36, 30 & 31 on East side of ridge near summit, from which	A fir, 6 in dia. bears N.10°E. 35 lks.
	A fir, 8 in dia. bears N.20°W. 56 lks.	
	No tree near in sections 31 & 36. Made mound of stone as per instructions.	
	This line on the South half passes over level land through timber consisting of fir & larch. The North half passes across head of canyon on toeridge. Sides of canyon on the South, timbered.	
	North on East boundary of Section 25.	Var.20° E.
40.00	Set post corner for $\frac{1}{4}$ section on steep mountain side on East side of ridge, from which	A pine, 36 in dia. bears S.2° E. 100 lks.
	A pine, 8 in dia. bears N.6° E. 50 lks	
80.00	Set post corner for sections 24, 25, 18 & 30 in ravine, course West. Deposited marked stone and raised stone mound as per instructions.	
	Land, broken & rocky. Timber in the canyons on South side, consisting of fir, larch & pine.	
	North on East boundary of section 24.	Var. 20° East.
40.00	Set post corner for $\frac{1}{4}$ section on on hill side, facing the East, from which,	
	A fir, 6 in dia. bears South E 50 lks. No tree near on West side.	
59.50	Small creek, 3 lks. wide, course NW.	