

Township 3 North, Range 36 East

<p>Chains 80.00</p>	<p>Set post corner for sections 13, 24, 18 & 19 on summit of ridge course, North West. Deposited stone & made stone mound as per instructions from which A pine, 8 in dia. bears N.16°W. 200 lks. A pine, 10 in dia. bears N.27°E. 210 lks. This line passes across deep canyon on the South side through thick timber, North side open, some grass, soil, stony.</p>	<p>+500</p>
<p>North on East boundary of Section 13.</p>		
<p>Var. 20° E.</p>		
<p>32.50</p>	<p>Boise City Stage road, course South of West.</p>	<p>-550</p>
<p>39.85</p>	<p>Umatilla River, course SW.</p>	<p>-6</p>
<p>40.00</p>	<p>Middle of river. Made corner for $\frac{1}{4}$ section, 60 links south of true corner on fir, 8 in dia. on left bank of the river, from which A fir, 7 in dia. bears S.20°W. 12 links. A fir, 10 in dia. bears N.85°E. 22 links.</p>	
<p>September 4th 1866.</p>		
<p>80.00</p>	<p>Set basalt stone 6x8x16, corner for sections 12, 13, 7 & 18, on steep mountain side, facing the south. This line passes over very broken lands. Timber along the Umatilla River, fir, pine & balm. The mountain sides on the South are bald, on the North timbered. All more or less rocky. The open lands have fair yield of grass.</p>	<p>+600</p>
<p>North on East boundary of Section 12.</p>		
<p>Var. 15° East.</p>		
<p>40.00</p>	<p>Set post corner for $\frac{1}{4}$ section on summit of ridge, course SW. Deposited marked stone and made stone mound as per instructions.</p>	<p>+400</p>
<p>80.00</p>	<p>Set post corner for sections 1, 12, 6 & 7 on hill side, facing the East, made stone mound as per instructions, after depositing marked stone. This line passes up mountain side from Umatilla River, some grass on the ridges. Soil, stony.</p>	<p>-100</p>