

Township 3 North, Range 36 East

Chains	<p>This line passes up Pine Creek, the bottom very narrow and crooked and the hillsides on the North, steep and rocky, without timber, on the South timbered, pine & fir.</p>	
40.00	<p>S.89°39'E. on North boundary of Section 5. Var. 21° East.</p> <p>Set post corner for $\frac{1}{4}$ section on hillside, facing the North, from which</p> <p>A larch, 8 in dia. bears N.75°E. 59 lks. A fir, 12 in dia. bears S.78°W. 42 lks.</p> <p>80.00 Set post corner for Sections 4, 5, 32 & 33 on hillside, facing the North, from which</p> <p>A fir, 18 in dia. bears North 20 lks. A fir, 10 in dia. bears N.50°W. 64 lks. A pine, 6 in dia. bears S.40°W. 18 lks. No tree near in section 4.</p> <p>This line passes over very broken hillside, facing the North. Scattering timber. Soil, stony.</p>	-150
3.00	<p>S.89°39'E. on North boundary of section 4. Var. 20° East.</p> <p>Pine Creek, channel, dry, course N.70°W.</p> <p>28.25 Pine Creek, channel dry, course SW.</p> <p>40.00 Set post corner for $\frac{1}{4}$ section, from which</p> <p>A pine, 36 in dia. bears South 7 lks. A pine, 24 in dia. bears N.85°W. 80 lks.</p> <p>80.00 Set post corner for Sections 3, 4, 33 & 34, from which</p> <p>A larch, 20 in dia. bears S.76°W. 20 lks. A larch, 10 in dia. bears N.40°E. 18 lks. A larch, 5 in dia. bears S. 3°E. 22 lks. No green tree near in section 33.</p> <p>This line passes up Pine Creek, the hillsides steep and rocky.</p> <p>Good grass on the summit to the North.</p>	-150 600
	<p>S.89°39'E. on North boundary of section 3. Var.20°East.</p>	