

Subdivisional Lines of Township 3 North, Range 36 E. W.M.

Chains	<p>Land: Surface, mountainous. Soil, 3rd, 2nd & small part on river bottom, 1st rate: Some good timber. Fir, tamarack, pine and balm: Alder & Willow underbrush; Grass in open glades.</p>
	<p>North between sections 13 and 14. Va. 18°45' East. Up irregular East hillside.</p>
40.00	<p>Set stone 14x12x4 on North side of ravine for $\frac{1}{4}$ sec. cor. †350 A pine, 16 in diam. brs. S. 64° E. 30 lks. dist.</p>
73.00	<p>Enter timber NE. & SW.</p>
80.00	<p>Set post on top of bluff for cor. to Sec. 11, 12, 13 and †700 14 from which A fir, 11 in diam. brs. N. 76° E. 20 lks. dist. A fir, 11 in diam. brs. S. 54° E. 30 lks. dist. A maple, 6 in diam. brs. S. 22° W. 30 lks. dist. A fir, 6 in diam. brs. N. 38° W. 33 lks. dist.</p>
	<p>Land; surface, steep bluff: Soil, 3rd rate, small part on top of bluff, 1st rate: good timber on N. 7 chs. Pine, tamarack and fir. Good bunch grass on open ground. October 1st 1878.</p>
	<p>East on a random line between Secs. 12 and 13. Va. 22° East.</p>
40.00	<p>Set post for temporary $\frac{1}{4}$ sec. cor.</p>
79.10	<p>Intersected E. boundary 468 lks. North of stone cor. to Sec. 12 and 13, from which cor. I run N. 86°39' West on a true line between Sec. 12 and 13 Va. 15° East.</p>
39.55	<p>Set stone 16x8x5 on rocky point for $\frac{1}{4}$ sec. cor. †400</p>
74.00	<p>Enter timber, NE. & SW.</p>
79.10	<p>The cor. to Sec. 11, 12, 13 and 14. †250 Land: Surface, mountainous: Soil, 3rd rate. Small part on top of bluff, 1st rate: Good timber on West 5 chs. Pine, tamarack and fir. Willow underbrush: Good bunch grass on open hillside.</p>