

Subdivisional Lines of Township 3 North, Range 36 E. W. M.

Chains	<p>North between Sections 11 and 12.</p> <p style="text-align: center;">Va. 22° East.</p> <p>40.00 Set spruce post for $\frac{1}{4}$ sec. cor.</p> <p style="padding-left: 40px;">A fir, 14 in diam. brs. N. 76°E. 94 lks. dist.</p> <p style="padding-left: 40px;">A fir, 9 in diam. brs. S. 45° W. 32 lks. dist.</p> <p>67.50 Road to timber, E. and W.</p> <p>80.00 Set tamarack post for corner to Sec. 1, 2, 11 and 12.</p> <p style="padding-left: 40px;">A fir, 15 in diam. brs. N. 16° E. 90 lks. dist.</p> <p style="padding-left: 40px;">A fir, 15 in diam. brs. S. 22° E. 121 lks. dist.</p> <p style="padding-left: 40px;">A fir, 12 in diam. brs. S. 34° W. 84 lks. dist.</p> <p style="padding-left: 40px;">A fir, 12 in diam. brs. N. 22° W. 112 lks. dist.</p> <p>Land: Surface, rolling: Soil, 2nd and 1st rate. Good Timber, tamarack, fir, pine and spruce; Some willow and other underbrush.</p> <p style="text-align: right;">Oct. 2, 1878.</p>
	<p>East on a random line between Sec. 1 and 12.</p> <p style="text-align: center;">Va. 21° East.</p> <p>40.00 Set post for temporary $\frac{1}{4}$ sec. cor.</p> <p>79.04 Intersected East Boundary 508 lks. North of corner to sections 1 and 12 from which corner I run N. 86°22' West on a true line between Sec. 1 and 12.</p> <p style="text-align: center;">Va. 16° East.</p> <p>4.00 Enter timber, N. & S.</p> <p>39.52 Set fir post for $\frac{1}{4}$ sec. cor.</p> <p style="padding-left: 40px;">A tamarack, 12 in di. brs. North 30 lks. dist.</p> <p style="padding-left: 40px;">A tamarack, 12 in di. brs. S. 32°W. 27 lks. dist.</p> <p>79.04 The cor. to Sec. 1, 2, 11 and 12.</p> <p>Land: Surface rolling: Soil, 2nd and 1st rate: good timber, tamarack, fir and pine: willow and other underbrush. Section 12 is nearly all well timbered and good soil.</p>