

Subdivisional Lines of Township 3 North, Range 36 E. W. M.

Chains	<p>A fir, 8 in. diam. brs. S. 41° W. 14 lks. dist. A fir, 8 in. diam. brs. N. 10° W. 8 lks. dist. Land; Surface, mountainous. Soil, 3rd and 2nd rate; good timber in places. Fir, tamarack & pine. Good bunch grass in open glades.</p>	
	<p>East on a random line between Sec. 23 and 26. Va. 15°30' East.</p>	
40.00	Set post for temporary $\frac{1}{4}$ sec. cor.	
79.64	<p>Intersected N. and S. line 28 lks. North of cor. to Sec. 23, 24, 25 and 26, from which cor. I run N.89°48' West on a true line between sections 23 and 26 Va. 22°15' East.</p>	
11.00	On ridge, N. & S.	+100
39.60	Brook, 6 lks. wide, course North.	-550
39.82	<p>Set stone 18x10x7 on west side of and near brook for $\frac{1}{4}$ sec. cor. A balm, 10 in diam. brs. N. 36° E. 47 lks. dist. A fir, 18 in diam. brs. S. 20° E. 11 lks. dist.</p>	
65.00	On spur extending North	+500
79.64	<p>The cor. to Sec. 22, 23, 26 and 27. Land; Surface, very broken and mountainous, soil 3rd rate; Scattering small groves of good timber; Pine, fir and tamarack; good grass in openings. About $\frac{1}{4}$ of sec. 26 is covered with timber</p>	-500
	<p>North between Sections 22 and 23. Va. 15°30' East.</p>	
	Down point of ridge.	
28.00	Umatilla River, 80 lks. wide, course NW.	-500
32.00	Road E. and W., Pendleton to La Grand.	
36.00	Steep bluff, course E. and W.	
40.00	<p>Set stone, 17x10x6 on steep South hillside for $\frac{1}{4}$ sec. cor. from which A pine, 18 in diam. brs. N. 5° E. 130 lks. dist.</p>	+80
79.50	Spring branch, course SE.	
80.00	Set stone 16x10x6 on SW. hillside above ravine for corner	-200