

Subdivisional Lines of Township 3 North, Range 36 E. W. M.

Chains					
	East on a random line between Sec. 2 and 11. Va. 21°15' East.				
40.00	Set post for temporary ¼ sec. cor.				
79.20	Intersected N. and S. line 18 lks. North of corner to Sec. 1, 2, 11 and 12, from which corner I run N.89°52' West on a true line between Sec. 2 and 11. Va. 21° East.				
29.00	Spring-branch, course South	-150			
39.60	Set fir post on E. hillside for ¼ sec. cor. from which A fir, 10 in diam. brs. N. 20° E. 36 lks. dist. A fir, 14 in diam. brs. S. 33° E. 77 lks. dist.		+100		
59.50	Road NW. & SE. to saw mill, located about 22 chs. South of quarter post.				
78.00	Brook, 8 lks. wide, course N. 70° W.				
79.20	The corner to Sec. 2, 3, 10 and 11. Land: Surface, hilly. Soil, 2nd and 1st rate; Timber was good, but had been nearly all cut and much of it destroyed: some willow & other underbrush.			-150	
	North on a random line between Sections 2 and 3. Va. 21°15' East.				
40.00	Set post for temporary ¼ sec. cor.				
74.80	Intersected North Boundary 130 lks. East of cor. to Sec. 2 and 3, from which corner I run S.00°56' East on a true line between Sec. 2 and 3. Va. 19° East.				
34.80	Set fir post for ¼ sec. cor. from which a Tamarack, 12 in diam. brs. S. 82° E. 48 lks. dist. Tamarack, 14 in diam. brs. West 20 lks. dist.				
55.00	Cabin bears S. 45° E.				
63.00	Road E. and W. to sawmill.				
70.00	Cabin brs. N. 32° E.				
74.50	Brook, 8 lks. wide, course West.				
74.80	The cor. to Sec. 2, 3, 10 and 11 Land; Surface, hilly: Soil, 1st & 2nd rate. Timber, some what scattering, having been cut and taken away; some			-150	