

Subdivisional Lines of Township 3 North Range 36 E. W. M.

Chains

Willow and other underbrush.

Oct 8th 1878

From the corner of sections 34 & 35 on the South Boundary of the Township, I run West and carefully measure along the South Boundary of Sec. 34 and at 72.50 to a point 22 lks. South of corner to Sec. 33 and 34, showing an error in measurement of 7.50 chains.

The post is standing and all the witness trees as described in the field notes.

I can see no way of remedy for this error. I therefore conclude to extend it to all the cross lines on this tier of sections to the North boundary of the Township.

North between Sections 33 and 34.

Var. 20°30' East.

Along East side of ridge

40.00 Set stone 18x10x8 on SE. hillside for $\frac{1}{4}$ Sec. cor. -150

A fir, 20 ins. diam. brs. N. 80° W. 70 lks. dist.

80.00 Set stone 18x10x8 on rocky point, facing SE. for cor. to -300

Sec. 27, 28, 33 and 34 from which a

Fir, 20 ins diam. brs. S. 12° E. 107 lks. dist.

Fir, 12 in diam. brs. S. 48° W. 96 lks. dist.

No trees on North side.

Land: Surface, mountainous. Soil 3rd rate; some good timber in scattering groves. Fir, tamarack and pine; grass in open ground.

Oct. 9th 1878.

East on random line between Sections 27 and 34.

Var. 17°30' East

40.00 Set post for temporary $\frac{1}{4}$ sec. cor.

72.60 Intersected N. and S. line 56 lks. North of corner to Sec. 26, 27, 34 and 35, from which cor. I run

N. 89°36' West on true line between sections 27 and 34

Var. 20° East