

Subdivisional Lines of Township 3 North, Range 36 E. W. M.

Chains		
	Sec. 22 on river bottom and on bluff South of river has quite a large amount of good timber. The bluff North of river do not have any timber.	
	North between Sections 15 and 16. Va. 18° East.	
8.04	To a point on Umatilla Indian Reservation line 5.25 lks. N. 20° East of 34th mile corner. Set stone 18x12x5 on ridge at reservation line. Marked (X) with cross for cor. to Sec. 15 and 16. Raised mound of stone in lieu of pits	+80
	West on a true line between Sec. 16 and 21. Va. 18° East.	
2.79	To a point S. 20° W. 3.30 chs. from 34th mile post on Indian reservation line; Set stone 15x12x10, marked X at point of intersection for corner to Sec. 16 and 21, raised mound of stone in lieu of pits. Oct. 14th 1878.	
	West on a true line between Sections 28 and 33. Va. 17°30' East.	
	Up South side of ridge.	
40.00	Set stone 18x12x5 near top of ridge for $\frac{1}{4}$ sec. cor.	+700
41.50	Top of ridge N. & S.	+20
59.88	To a point on reservation line 13.98 chs. S. 20° W. of 36th mile post on the E. boundary of reservation; Set stone 18x10x10, marked X at Reservation line for corner to Sec. 28 and 33, raised mound of stone in lieu of pits. Land, Surface, mountainous. Soil 3rd rate; no timber; good grass.	-150
	West on a true line between Sectios 21 and 28. Va. 20°30' East.	
5.00	Creek bottom, N. & S.	-150
8.00	Creek, 28 lks. wide, course North	
9.00	Steep bluff, N. & S.	