

Subdivisional Lines of Township 3 North, Range 36 E. W. M.

<p>Chains 80.00</p>	<p>A fir, 16 in diam. for corner to sections 3, 4, 9 and 10 on NW. hillside from which a Tamarack, 18 in diam. brs. N. 56° E. 36 lks. dist. Tamarack, 5 in diam. brs. S. 34°W. 21 lks. dist. Fir, 36 in diam. brs. N. 70° W. 26 lks. dist. Land; Surface, hilly; Soil, 3rd, 2nd and 1st rate; Scattering timber on West $\frac{1}{2}$ mile E. $\frac{1}{2}$ mile nearly all open. All of Sec. 10 South of brook has good timber.</p>	
	<p>Oct. 18th 1878</p>	
	<p>South between sections 9 and 10.</p>	
	<p>Va. 21° East.</p>	
<p>22.00</p>	<p>Brook 10 lks. wide, course West. Also enter timber E. & W.</p>	<p>-300</p>
<p>40.00</p>	<p>Set fir post for $\frac{1}{4}$ sec. cor. on North hillside from which which a Fir, 15 in diam. brs. S 78° E. 72 lks. dist. Fir, 14 in diam. brs. N. 60° W. 43 lks. dist.</p>	<p>+250</p>
<p>64.15</p>	<p>To a point on Indian Reservation 36.20 chs. West -(by the meanders) of 33rd mile post. Set fir post in mound of stone for corner to Sections 9 and 10 at point of intersections from which a Fir, 10 in diam. brs. N. 78° E. 23 lks. dist. Fir, 10 in diam. brs. N. 32° W. 65 lks. dist. Land: Surface, hilly. Soil, 2nd and 1st rate. Good timber South of brook. Tamarack, fir and pine; good grass in open ground.</p>	<p>-150</p>
	<p>North on a random line between Sections 3 and 4.</p>	
	<p>Va. 21° East.</p>	
<p>40.00</p>	<p>Set post for temporary $\frac{1}{4}$ sec. cor.</p>	
<p>75.22</p>	<p>Intersected North Boundary 175 lks. East of corner to Sec. 3 and 4, from which cor. I run S. 1°16' East on true line between sections 3 and 4.</p>	
	<p>Va. 20° East.</p>	
<p>35.22</p>	<p>Set tamarack post on level ground for $\frac{1}{4}$ sec. cor from which a</p>	