

Subdivisional Lines of Township 3 North, Range 36 E. W. M.

Chains	<p>Pine, 24 in diam. brs. S. 68° E. 50 lks. dist.</p> <p>Fir, 10 in diam. brs. S. 74° W. 95 lks. dist.</p> <p>53.00 Road, E. &amp; W. to timber.</p> <p>75.22 The cor. to Sec. 3, 4, 9 and 10.</p> <p>Land: Surface, hilly; Soil, 2nd and 1st rate: has been good timber, but a large and the best part of it is cut and used and much has been wastefully destroyed.</p> <p style="text-align: right;">Oct. 19th 1878.</p>	
	<p>West on a true line between Sec. 4 and 9.</p> <p style="text-align: right;">Va. 21° East.</p>	
40.00	<p>Set tamarack post for <math>\frac{1}{4}</math> sec. cor.</p> <p>Pine, 28 in diam. brs. East 72 lks. dist.</p> <p>Tama., 13 in diam. brs. N. 46° W. 27 lks. dist.</p>	-100
46.00	<p>Brook, 12 lks. wide, course NW.</p>	-200
60.50	<p>Road, N. &amp; S. to timber</p>	+150
68.50	<p>Road, NE. &amp; SW. to timber.</p>	
80.00	<p>Set fir post in shallow ravine for cor. to Sec. 4, 5, 8 &amp; 9.</p> <p>A fir, 34 in diam. brs. N. 40° E. 6 lks. dis.</p> <p>A fir, 14 in diam. brs. S. 64° E. 34 lks. dis.</p> <p>A fir, 16 in diam. brs. S. 16° W. 46 lks. dis.</p> <p>A fir, 15 in diam. brs. N. 42° W. 50 lks. dis.</p> <p>Land: Surface, hilly: Soil, 1st &amp; 2nd rate; good timber</p> <p>West of brook: East of brook, scattering fir, tamarack and pine. Some willow &amp; other underbrush. Good grass in openings.</p>	
	<p>North on a random line between Sec. 4 and 5.</p> <p style="text-align: right;">Va. 21°10' East.</p>	
40.00	<p>Set post for temporary <math>\frac{1}{4}</math> sec. cor.</p>	
75.46	<p>Intersected North Boundary 192 lks. East of cor. to Sec. 4 &amp; 5, from which cor. I run</p> <p>S. 1°22' East on a true line between Sections 4 and 5.</p> <p style="text-align: right;">Va. 20° East.</p>	
15.50	<p>Top of bluff.</p>	+500