

Subdivisional Lines of Township 3 North, Range 36 E. W. M.

Chains		
	<p>No trees on North side.</p> <p>Land: Surface, E. <math>\frac{1}{2}</math> mile undulating W. <math>\frac{1}{2}</math> mile steep hill-side: Soil, 1st, 2nd and 3rd rate; good timber East of brook, fir, tamarack and pine: good grass.</p>	
	<p>South between Sec. 7 and 8.</p> <p style="text-align: center;">Va. 19° East.</p>	
44.50	Brook, 15 lks. wide, co. West.	-150
12.50	Top of bluff.	+350
29.00	Alonzo Barry's cabin, 100 lks. West of line and plowed field East.	
40.00	<p>Set pine post on level for <math>\frac{1}{4}</math> sec. cor.</p> <p>Pine, 30 in diam. brs. N. 66° E. 87 lks. dist.</p> <p>Pine, 20 in diam. brs. West 30 lks. dist.</p>	
80.00	<p>Set pine post for corner to Sec. 7, 8, 17 and 18 from which a</p> <p>Pine, 30 in diam. brs. N. 45° W. 5 lks. dist.</p> <p>Pine, 24 in diam. brs. S. 36° W. 12 lks. dist.</p> <p>No trees near in Sec. 8 and 17.</p> <p>Land; Surface S. 68 chs. rolling. N. 12 chs. steep hill-side: Soil, 1st, 2nd and 3rd rate; Timber, good in places. Scattering pine, fir and tamarack; Good grass. Most of this mile is good farming land.</p>	
	<p>East between Sec. 8 and 17.</p> <p style="text-align: center;">Va. 21<math>\frac{1}{2}</math>° East.</p>	
39.35	<p>To a point on reservation line 32.95 chs. East of 30th mile post, measured along the meanders of said line.</p> <p>Set pine post at point of intersection with the line of the Umatilla Indian reservation for corner to Sec. 8 and 17 from which a</p> <p>Fir, 11 in diam. brs. N. 50° W. 24 lks. dist.</p> <p>Tamarack, 18 in diam. brs. S. 2° W. 22 lks. dist.</p> <p>Land: Surface, rolling: Soil, 1st and 2nd rate: scattering pine, timber: good bunch grass: well adapted to farming.</p>	