

Subdivisional Lines of Township 3 North, Range 36 E. W. M.

Chains	<p>South between Sec. 17 and 18.</p> <p style="text-align: center;">Va. 21° East.</p>	
27.71	<p>To a point 19.56 chs. S. 57° 30' West of 30th mile post on the line of the Umatilla Indian Reservation: Set pine post at point of intersection for corner to Sec. 17 and 18. Raised mound of stone around stake in lieu of pits.</p> <p>Land: Surface hilly. Soil, 1st and 2nd rate: only a few scattering trees. Good grass. Good for farming.</p> <p style="text-align: center;">October 21st 1878</p>	-200
	<p>West on a random line between Sec. 7 and 18.</p> <p style="text-align: center;">Va. 21° East.</p>	
40.00	Set post for temporary $\frac{1}{4}$ sec. cor.	
68.05	<p>Intersected West Boundary 285 lks. South of cor. to Sec. 7 and 18 from which cor. I run S.87°58' East on a true line between Sec. 7 and 18 Va. 21° East.</p>	
28.05	Set stone 18x14x4 in plowed field for $\frac{1}{4}$ sec. cor.	+400
49.00	James Salery's house on line.	
68.05	<p>The cor. to Sec. 7, 8, 17 and 18.</p> <p>Land: Surface W. <math>\frac{1}{2}</math> mile, steep hillside; E. <math>\frac{1}{2}</math> mile, undu- lating; Soil, 1st and 2nd rate; Scattering pine tim- ber; good grass; good farming land.</p>	
	<p>West on a random line between Sections 6 and 7.</p> <p style="text-align: center;">Va. 19° East.</p>	
40.00	Set post for temporary $\frac{1}{4}$ sec. cor.	
67.86	<p>Intersected West Boundary 3.20 lks. South of cor. to Sec. 6 and 7 from which cor. I run S.87°43' East on a true line between Sec. 6 and 7. Va. 20° East.</p>	
5.00	House bears N. 78° E.	
15.00	House bears N. 85° W.	
27.86	Set stone 18x10x7 near top of hill for $\frac{1}{4}$ sec. cor.	+100
41.00	Fence and field, N. & S.	
67.86	The cor. to Sec. 5, 6, 7 and 8.	-150