

## Subdivisional Lines of Township 3 North, Range 36 E. W. M.

Chains	East on random bett. Secs. 9 and 16. Va. 19° East.	
40.00	Set temporary $\frac{1}{4}$ Sec. cor. and at	
79.14	Intersect E. bdy. 200 lks. N. of cor. to Secs. 9, 10, 15 and 16. Thence N 89°34' W. on true line. Va. same.	
21.25	Head of canyon S.	-50
33.00	Wagon road, S. 78° W.	
39.57	Set post 4 ft. long 3 ins. square, 24 ins. in the ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ S. on N. face, from which A tamarack, 4 ins. diam. bears N. 5° E. 6 lks. dist., marked $\frac{1}{4}$ S B T. A tamarack, 6 ins. diam. bears S 85° W., 19 lks. dist., marked $\frac{1}{4}$ S B T.	
54.50	Wagon road, SW.	
68.50	Wagon road, S.	
79.14	Cor. to Secs. 8, 9, 16 and 17. Land rolling. Soil 2nd rate. Heavy pine, tamarack and fir with underbrush of same. 79.14 chs.	
	West on ran. bet. Secs. 8 and 17. Va. 19° East.	
40.00	Set temporary $\frac{1}{4}$ sec. cor. and at	
41.45	A point, 164 N. of Meander cor. to fractional Secs. 8 and 17. Thence N. 87°43' East on true line. Va same	
1.45	Set post 3 ft. long, 3 ins. square, 24 ins. in the ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ S on N, face, from which A fir, 7 ins. diam. bears S 75° W. 50 lks. dist., marked $\frac{1}{4}$ S B.T. A fir, 7 ins. diam. bears N. 83° W. 50 lks. dist. marked $\frac{1}{4}$ S B T.	
41.45	Cor. to Secs. 8, 9, 16 and 17. Land, rolling, Soil 2nd rate. Heavy pine, fir and tamarack with underbrush. 41.45 chs.	