

766

Chains 69.90	Wagon road, E. and W.	
79.47	To cor. to Secs. 16, 17, 20 and 21. Land, broken and mountainous. 79.47 chs. Soil, 3rd rate. Timber; pine and fir and underbrush. Good grass.	
North bet. Secs. 31 and 32. Va. 13° East.		
10.00	Meacham Creek, N. 20° East.	-50
19.00	Same " N. 20° W.	-50
29.50	Same " N. 45° E.	-30
40.00	Set post, 3 ft. long, 3 ins. square, 24 ins. in the ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ S on W. face, from which A fir, 36 ins. S. 70° E. dist. 25 lks., marked $\frac{1}{4}$ S B T. A pine, 30 ins. in diam. bs. N. 85° W. dist. 20 lks., marked $\frac{1}{4}$ S B T.	
44.50	Meacham Creek, 30 lks. NW.	
57.50	Same " 30 lks. NE.	
61.50	Same " 30 lks. NW.	
76.50	House in small inclosure.	
80.00	Set post, 4 ft. long, 4 ins. square, 24 ins. in the ground for cor. to Secs. 29, 30, 31 and 32, marked T 3 N S 29 on NE., R 36 E S 32 on SE., S 31 on SW. and S 30 on NW. faces, with 1 notch on S. and 5 notches on E. edges from which A pine, 16 ins. diam. bears S. 25° W. 57 lks. dist., marked T 3 N R 36 E S 31 B T. A birch, 5 ins. diam. bears N. 15° W. 38 lks. dist., marked T 3 N R 36 E S 30 B T. No other trees in limits and raised mound of stone over it. Land, mostly creek bottom. Soil, 2nd rate, gravelly. Dense brush, pine & Balm timber. 80.00 chs.	
East on ran. bet. Secs. 29 and 32.		