

Subdivisional Lines of Township 3 North, Range 36 E. W. M.

Chains	21, 28 and 29. Thence S. 89°56' W. on true line. Va. 20° East.	
5.75	Gulch, SW.	-25
18.00	Spring branch, SE.	
24.00	Summit of ridge.	+400
28.85	Canon, SE.	-400
40.00	Set basalt stone 12x8x6 ins. 8 ins. in the ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on N. face, and raised mound of stone $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.	
49.00	Summit, ridge, S.	+250
53.85	Gulch, S.	-200
68.00	Summit of ridge, S.	+300
77.00	Spring, branch SE.	
80.00	Cor. to Secs. 19, 20, 29 and 30. Land, rough and mountainous. 80 chs. Soil, 3rd rate and rocky. No timber.	
	West on ran. bet. Secs. 19 and 30. Va. 19° East.	
40.00	Set temporary $\frac{1}{4}$ sec. cor. and at	
79.20	Intersect W. bdy. Township at cor. to Secs. 19 and 30, 24 and 25. Thence East on true line. Va. same.	
33.50	Canon, S.	-150
39.20	Set basalt stone 12x10x8 ins. 8 ins. in the ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on N. face and raised mound of stone over it.	
45.00	Summit of ridge, S.	+50
52.00	Canon, S.	-150
60.00	Summit ridge.	+150
79.20	Cor. to Secs. 19, 20, 29 and 30. Land, mountainous. 79.20 chs. Soil, 3rd rate and rocky. Good bunch grass.	