

Subdivisional Lines of Township 3 North, Range 36 E. W. M.

Chains		
	North bet. Secs. 19 and 20.	
	Va. 19° East.	
1.75	Canon East	-200
10.50	Summit of ridge, E.	+200
19.90	Canon, E.	-150
40.00	Set basalt stone for $\frac{1}{4}$ sec. cor. 18x10x8 ins. 12 ins. in the ground, marked $\frac{1}{4}$ on W. face, and raised mound of stone over it.	+500
47.00	Enter timber.	
59.20	Draw, W.	-20
80.00	Set post 4 ft. long, 4 ins. square., 24 ins. in the ground for cor. to Secs. 17, 18, 19 and 20, marked T 3 N R 36 E S 17 on NE., R 36 E S 20 on SE., S 19 on SW. and S 18 on NW. faces with 3 notches on S and 5 notches on E. edges, from which A pine, 20 ins. diam. bears S. 5° W. 76 lks. marked T 3 N R 36 E S 19 B T. A pine, 36 ins. diam. bears N. 80° W. 140 lks. dist., marked T 3 N R 36 E S 18 B T. A pine, 16 ins. diam. bears N. 60° E. 127 lks. dist., marked T 3 N R 36 E S 17 B T. Land, rough and mountainous. 80 chs. Soil, 2nd rate. Good grass. Pine timber on N. $\frac{1}{2}$ of line.	
	East on ran. bet. Secs. 17 and 20.	
	Va. 22 $\frac{1}{2}$ ° East.	
40.00	Set temporary $\frac{1}{4}$ sec. cor. and at	
79.80	Intersect N. and S. line 35 lks. N. of cor. to Secs. 16, 17, 20 and 21. Thence N. 89°45' W. on true line.	
	Va. 20° East.	
2.50	Summit of ridge, S.	+40
12.80	Canon, S.	-250
19.80	Summit, ridge,	+50
26.75	Canon, S.	-100
39.90	Set basalt stone, 14x12x10 ins. 8 ins. in the ground for	