

Alletment.

Section 18

Subdivision of Township 3 North Range 36 East

Chains

19.25 A pine, 36 ins. diam., which I mark 1/32 S. on N. face, for 1/32 Sec corner, from which  
 A pine, 36 ins. diam., brs. N. 45° E. 63 lks. dist. marked 1/32 S B T.  
 A fir, 25 ins. in diam., brs S 36° W. 54 lks. dist. marked 1/32 S B T.

Thence along steep bank of Wild Horse creek. Heavy timber and brush.

36.00 Canyon course N. W.

-75

39.25 Set basalt stone 16x12x6 ins. 12 ins. in the ground for 1/32 on N. face, from which  
 A pine, 20 ins. diam. brs North 44 lks. dist. marked 1/32 S. B. T.  
 A pine, 40 ins. diam., brs N. 4° W. 44 lks. dist. marked 1/32 S B T.

Land rolling & hilly.

E. 25 chs. Heavy timber.

From the 1/32 & 1/16 corner 20 chs. N. of the corner to Secs. 13, 18, 19 & 24 on W. bdy. of Tp.

I run

S. 89°28' E. on true line in Sec. 18.

Var. 19°30' East.

Along Summit through Sunflower.

19.25 Set basalt stone 18x18x6 ins. 12 ins. in the ground for 1/16 & 1/32 Sec. corner marked 1/16 on S & 1/32 on N. faces, dug pits 18x18x12 ins. E & W. of stone 5½ ft. dist. and raised mound of earth 1½ ft. high 3½ ft. base over it.

Along summit of mountain through scattering Pine & Fir.

39.25 Set basalt stone 18xx8x4 ins. 14 ins. in the ground for 1/16 & 1/32 Sec. corner marked 1/16 on S and 1/32 on N. face, dug pits 18x18x12 ins. E. & W. of stone 5½ ft. dist. and raised mound of earth 1½ ft. high 3½ ft. base over it.