

Alletment.

Section 18

Subdivision of Township 3 North Range 35 East.

<p>Chains 49.25</p>	<p>Set basalt stone 14x16x7 ins. 9 ins. in the ground for 1/32 Sec. corner; marked 1/32 on N. face, dug pits 18x18x12 ins. E. & W. of stone 5 1/2 ft. dist. & raised a mound of earth 1 1/2 ft. high 3 1/2 ft. base over it, from which,</p> <p>A pine, 36 ins. diam. brs West 10 lks. dist. marked 1/32 S B T.</p> <p>Land rolling Summit.</p> <p>Scattering pine timber.</p> <p>Soil, 1st rate.</p> <p>Good grass.</p>
<p>10.00</p>	<p>From the 1/4 Sec. cor. between Secs. 18 & 19.</p> <p>I run</p> <p>S. 89°28'E. on true line between Secs. 18 & 19.</p> <p style="text-align: right;">Var. 20°39'E.</p> <p>Set basalt stone 10x8x7 ins. 6 ins. in the ground for 1/32 Sec. corner marked 1/32 on N. face, dug pits 18x18x12 ins. E. & W. of stone 5 1/2 ft. dist. and raised a mound of earth 1 1/2 ft. high 3 1/2 ft. base over it.</p> <p>Land, rolling summit.</p> <p>Scattering pine timber.</p> <p>Soil 1st rate.</p> <p>Good grass.</p>
<p>20.00</p> <p>20.00</p> <p>20.00</p>	<p>From the 1/32 Sec. corner 10 chs. E. of 1/4 Sec. corner between Secs. 18 & 19.</p> <p>I run</p> <p>North on random line in Sec. 18.</p> <p>Intersect the E. & W. line at 1/32 Sec. corner 10 chs. E. & 20 chs. N. of 1/4 Sec. corner between Secs. 18 & 19.</p> <p>Thence I run</p> <p>South on true line in Sec. 18.</p> <p style="text-align: right;">Var. 19° E.</p> <p>The 1/32 Sec. corner 10 chs. E. of 1/4 Sec. corner between Secs. 18 & 19.</p>