

Section 19

Subdivision of Township 3 North Range 36 East

Chains 60.00	Set basalt stone 12x12x6 ins. 8 ins. in the ground for 1/16 Sec. corner marked 1/16 on W. face, dug pits 18 18x12 ins. N. & S. of stone 5½ ft. dist. raised a mound of earth 1½ ft. high 3½ ft. base over it.
80.00	The corner to Secs 19, 24, 25 & 30 which is a basalt stone 12x16x8 ins. 8 ins. in the ground marked 4 notches on N. & 2 notches on the South edges & pits 18x18x12 ins. in each. Sec. 5½ ft. dist. & mound of earth 2 ft. high 4½ ft. base alongside. Land, rolling. Soil 1st rate but rocky in places. Timber in Gulch. Good grass and sunflower.
39.80	From the corner to Secs. 19, 24, 25 & 30 on the W. bdy. of Tp. I run East on random line between Secs. 19 & 30. Var 19° E. Setting temporary 1/16 Sec. corner at 19.20 chains. And at Intersect the ¼ Sec. corner between Secs. 19 & 30, which is a basalt stone 12 x 10x8 ins. 8 ins. in the ground marked ¼ on N. face & mound of stone over it. Thence I run West on true line between Sections 19 & 30. Var. 19° E.
5.70	Canyon Course S.
20.00	Set basalt stone 12x9x8 ins. 8 ins. in the ground for 1/16 Sec. corner marked 1/16 on N. face, and raised mound of stone over it. Pits impracticable.
39.80	To the corner of Secs. 19, 24, 25 & 30. Land rolling & break off to the Umatilla River South. Soil, rocky except near the Sec. corner, some grass.