

Subdivision of Township 3 North Range 36 East

Chains	<p>Thence I run S 89°43' W. on true line. Through the Center of Sec. 19.</p>
20.00	<p style="text-align: right;">Var. 19° E.</p> <p>Set post 3 ft. long 3 ins. square with a charred knot 12 ins. in the ground for 1/16 Sec, corner marked 1/16 S. on N. face, dug pits 18x18x12 ins. E. &amp; W. of post 5½ ft. dist. &amp; raised mound of earth 1½ ft. high 3½ ft. base around post.</p>
21.50	<p>Enter pine Timber and ascend.</p>
40.00	<p>Set basalt stone 10x9x4 ins. 6 ins. in the ground for ¼ Sec. corner marked ¼ on N. face, &amp; raised a mound of stone over it.</p>
	<p>Pits impracticable.</p>
45.00	<p>Dry Gulch South.</p>
60.00	<p>Set basalt stone 12x9x8 ins. 8 ins. in the ground for 1/16 Sec. cor. marked 1/16 on N. face, dug pits 18x18x 12 ins. E. &amp; W. of stone 5½ ft. dist. raised mound of earth 1½ ft. high 3½ ft. base over it.</p>
60.75	<p>Gulch course S. W.</p>
79.30	<p>To the ¼ Sec. corner between Sec. 19 &amp; 24 on W. bdy. of Tp.</p>
	<p>Land rolling. Soil 1st rate, except some rocky, washed out places. Good grass and sunflower.</p>
	<p>From the 1/16 Sec. cor. 20 chs. N. of ¼ Sec. corner, bet. Sec. 19 &amp; 24 on W. bdy. of Tp.</p>
	<p>I run S. 89° 28' East on true line Sec. 19.</p>
	<p style="text-align: right;">Var. 20° E.</p>
	<p>Over rolling ground.</p>
19.30	<p>Set basalt stone 10x8x7 ins. 6 ins. in the ground for 1/16 &amp; 1/32 Sec. corner marked 1/16 on S. &amp; 1/32 on N. face, dug pits 18x18x12 ins. E. &amp; W. of stone 5½ ft.</p>