

Township No.3 North, Range No.37 E., Willamette Meridian

54.00	A Spruce, 8 ins. in diam., bears S.15°W. 42 Lks.dist. Brook; 6 lks.wide, course S.W.
80.00	The corner to Townships 3 & 4 N., Ranges 37 & 38 E. W.M. Land: Surface , undulating. Soil, 2nd & 3rd rate. Good timber, Fir, Tamarack, Spruce & Pine. <p style="text-align: right;">April 24, 1879.</p>
<p>General Description.</p> <p>The surface of this Township is generally very broken and mountainous. The North half has some nearly level plateaus The soil is mostly 3rd rate and stony. Large part worthless. Some along the river and on the plateau on the N. part good 2nd rate.</p> <p>There is mostly good timber on the North slopes and on level plateaus. The timber is Fir, Pine, Tamarack and Spruce. South slopes are generally covered with good grass. There are several settlers in the North half of this Township.</p>	
<p><i>Sub. Survey, T.3 N., R. 37 E., Sec. 18, 19 #340 - dated Sept. 26 - 1879</i></p>	
<p>I begin at the post in the mound of Stone, the Corner of Sec. 18 & 19 on the West Boundary of the Township and with Burts Improved Solar Compass, I run and measure East, retracing the line between Sec. 18 & 19.</p>	
<p>Var.</p>	
40.00	Cannot find any trace of $\frac{1}{4}$ Sec. Corner.
80.00	To a point 105 Lks. nearly South of Witness tree, which was blazed and marked on the South side, showing plainly that this tree is North instead of East from the Cor. as stated in the field notes of Original Survey. No trace of any Cor. except Witness tree. Drove Stake at point of old Corner.
<p>Thence; North between Sec. 17 & 18</p>	
<p>Var.</p>	
40.00	A Fir tree and two Witness trees, as described in field Notes.

*189-445
1879-192*