

Chains	<p>A Fir, 8 ins. in diam., bears S. 55°E., 194 Lks. dist. A Pine, 16 " " " " S. 30°W., 91 " "</p> <p>No tree near on N.W.</p> <p>Land; surface mountainous. Soil 3rd rate. Several thick strips of timber in ravines. Mostly open hillside, Fir, and Pine. Good grass in open ground.</p>	
	<p>S. 89°45' W. on a true line along the S. Boundary of Sec. 16 Var. 19°00' E.</p>	
6.00	Heavy timber.	
30.00	Road from Pendleton to La Grande, course S.E. & N.W.	
32.00	Umatilla River from S.E. to W	-300
39.00	" " " W. to N.W., 80 lks. wide.	
40.18	Set Basalt Stone 17 x 10 x 5 on level river bottom for $\frac{1}{4}$ Sec. Cor.	
	<p>A Fir, 28 ins. in diam., bears N. 40°W., 25 Lks. dist. A Maple, 6 " " " " S. 24 " "</p>	
48.00	Leave bottom, course S.E. & N.W.	
80.35	Set Basalt Stone 16 x 12 x 7 on N.W. face of Spur for Cor. to Secs. 16, 17, 20 & 21.	+500
	<p>A Fir, 24 ins. in diam., bears N. 48° E., 166 Lks. dist. No other trees near.</p> <p>Land; surface mostly mountainous, small part on river nearly level. Soil 3rd & 2nd rate. Mostly heavy timber, Fir, Pine, Tamarack & Balm. Some underbrush.</p>	
	<p>S. 89° 45' W. on a true line along the S. Boundary of Sec. 17. Var. 13° 00' E.</p>	
29.000	Deep Gulch opens N.E.	-350
40.18	Set Basalt Stone 28 x 14 x 7 on E. side of Spur, in open Glade for $\frac{1}{4}$ Sec. Cor. No trees near.	
58.00	Leave timber, course N. & S.	
62.00	On main Ridge, course N.W. & S.E.	+900
80.35	The Cor. to Secs. 17, 18 19 & 20	-350
	<p>Land; surface mountainous. Soil; 3rd rate. Some heavy timber but mostly open mountainside. Fir, pine & Tamarack</p>	