

Township 3 N., R. 37 E., W.M.

Chains 40.90	Set a Basalt Stone, 18 x 14 x 5 on E. side of small Ravine for $\frac{1}{4}$ Sec. Cor. A fir, 28 ins. diam., bears S.74°E., 48 lks. dist. " " 40 " " " S.42°W., 31 " "	
66.50	Brook, 6 lks. wide, course S.W.	±500
80.90	The Cor. to Secs. 3, 4, 9 & 10 Land; Surface mountainous. Soil; 3rd rate. Grass in openings. Some brush, Heavy timber with open glades, tamarack, fir and pine.	±300
	Oct. 23, 1879.	
	North between Secs. 16 & 17. Var. 13° 00' E.	
22.25	Umatilla River, 75 lks. wide, course N.W.	-300
29.00	Toll road to La Grande, N.W. & S.E.	
33.00	Foot of bluff and leave timber N.W. & S.E.	
40.00	Set Basalt Stone, 16 x 12 x 10 on steep S.W. face of bluff for $\frac{1}{4}$ Sec. Cor. No trees.	
80.00	Set Basalt Stone, 17 x 8 x 6 and post in mound of stone on steep S. side of Spur, for Cor. to Secs. 8, 9, 16 & 17. No trees. Land; Surface mountainous, small part on river level. Soil, 3rd rate, small part on river bottom, 1st rate. Heavy timber in river bottom, S. of river good in places; Fir, tamarack, pine and balm. Some underbrush.	±800
	East on a random line between Sec. 9 & 16. Var. 19° 30' E.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.48	Intersected N. and S. line, 56 lks. S. of Cor., to Secs. 9, 10, 15 and 16, from which 10, 15 and 16, from which Cor., I run S. 89° 36' W. on a true line, 56 lks. S. of Cor. to Secs. 9, & 16. Var. 23° 30' E.	
6.00	Timber, course N. & S.	
8.00	In deep Gulch, opens S.	-150