

Township 3 N., R. 37 E., W.M.

Chains	East on a random line between Sec. 8 & 17. Var. 19° 30' E.	
40.00	Set post for temporary $\frac{1}{4}$ Sec. Cor.	
80.28	Intersected N.&S. line 72 lks. S. of Cor. to Sec. 8, 9, 16 & 17, from which Cor., I run S. 89° 29' W. on a true line between Sec. 8 & 17. Var. 19° 30' E.	
40.14	Set Basalt Stone 17 x 8 x 6 on steep W. face of Spur for $\frac{1}{4}$ Sec. Cor. A Fir, 28 ins. in diam., bears N. 8° W., 306 lks. dist. A Pine, 18 " " " " S. 12° E., 54 " "	
43.00	Enter heavy timber, course N.&S.	
47.00	Brook, 12 lks. wide, course South	-750
48.500	Leave heavy timber, course N.&S.	
80.28	The Cor. to Sec. 7, 8, 17 & 18. Land; Surface mountainous. Soil, 3rd rate. Heavy timber on brook, remainder scattering E 40 chains open. Good grass.	+150
	North between Sec. 7 & 8. Var. 19° 30' E.	
28.00	On Spur, extending S.W.	+400
40.000	Set Basalt Stone 20 x 8 x 5 on N.W. face of Bluff for $\frac{1}{4}$ Sec. Cor. A Fir, 16 ins. in diam., bears S. 18° E., 93 lks. dist. " " 22 " " " " S. 12° W., 105 " "	
43.50	Gulch and Spring branch, course S.W.	-200
80.00	Set Basalt Stone 16 x 8 x 7 and post in mound of stone on steep S. face of Bluff for Cor. to Sec. 5, 6, 7 & 8 No trees. Land; Surface mountainous. Soil, 3rd rate. Some scatter- ing Pine and Fir timber, but mostly open. Good grass.	+600
	East on a random line between Sec. 5 & 8. Var. 19° 45' E.	