

|        |  |      |
|--------|--|------|
| Chains |  |      |
| 40.00  | Set post for temporary $\frac{1}{4}$ Sec. Cor.   |      |
| 80.42  | Intersected N.&S. line 96 lks. S. of Cor. to Secs. 4, 5<br>8 & 9, from which Cor.,<br>I run<br>S. 89° 19' W. on a true line between Sec. 5 & 8.<br>Var. 20° 15' E.       |      |
| 40.21  | Set Basalt Stone 16 x 12 x 10 in mound of stone in deep<br>Gulch for $\frac{1}{4}$ Sec. Cor.<br>A Balm, 6 ins. in diam., bears N. 6° E. 61 lks. dist.<br>No other trees. | -400 |
| 80.42  | The Cor. to Sec. 5, 6, 7 & 8.<br>Land; Surface mountainous. Soil, 3rd rate. No timber.<br>Good grass.  | +450 |
|        | West on a random line between Sec. 6 & 7.<br>Var. 19° 45' E.   |      |
| 40.00  | Set post for temporary $\frac{1}{4}$ Sec. Cor.   |      |
| 79.84  | Intersected West Bdy. 102 lks. N. of Cor. to Sec. 6 & 7<br>from which Cor.,<br>I run<br>N. 89° 16' E. on a true line between Sec. 6 & 7.<br>Var.                         |      |
| 16.00  | Deep Gulch and Spring branch, opens South  | -450 |
| 36.50  | On Bluff   | +450 |
| 39.84  | Set Basalt Stone 14 x 12 x 8 on S. face of Bluff in<br>mound of stone for $\frac{1}{4}$ Sec. Cor.  |      |
| 79.84  | The Cor. to Sec. 5, 6, 7 & 8<br>Land; Surface Mountainous. Soil, 3rd rate. Good grass.<br>Some Fir, Pine & Tamarack timber in Gulch on W. $\frac{1}{2}$ mi.              |      |
|        | North on random line between Sec. 5 & 6.<br>Var. 19° 45' E.  |      |
| 40.00  | Set post for temporary $\frac{1}{4}$ Sec. Cor.   |      |
| 78.70  | Intersected N. Bdy. 88 lks. W. of Cor. to Sec. 5 & 6,<br>from which, Cor.  |      |