

Resurvey of the East Boundary of Township 3 N., R.37 E., W.M.
 Surveyed by William E. Campbell under Contract 718
 Survey commenced July 24, 1900
 Survey completed August 29, 1900.

Chains	
	<p>The S.E. Cor. of T.3 N., R.37E., is a Basalt Stone, 18 x 10 x 8 ins., set in a mound of stone, on level, open glade, marked and witnessed as described by the Surveyor-General, as Cor. of two Tps.</p> <p>I destroy the marks on the S.W. witness tree and such marks on the Cor. Stone as pertains to Tp.2 N., R.38 E. viz: 6 notches on S. & E. edges and the numbers 2 N., 38E., on S.E. face.</p> <p>Thence, I run North, between Secs. 1 & 36. Over level, grassy land, through scattering timber.</p>
6.55	<p>The closing Cor. of T. 3 N., R.38 E.</p> <p>Thence, I run N. 0° 18' E., between Secs. between Secs. 31 & 36.</p>
7.55	<p>Descend gradually.</p>
12.50	<p>Enter heavy timber and undergrowth.</p>
40.00	<p>A point, 100 ft. below the Tp. Cor. and the $\frac{1}{4}$ Sec. Cor. E. Bdy. of Sec.36, a Spruce, grown to 8 ins. diam., marked and witnessed as described by the Surveyor-General.</p> <p>Thence I run N. 1°03' E.</p>
49.20	<p>July 26: At this point I set off, 19° 25' 30" N. on the decl. arc and at oh, 6m. P.M., l.m.t., observe the sun on the meridian; the resulting lat. is a little less than 45°42'.</p> <p>Abrupt descent of heavily timbered mountain, bears N.70° W. and S.70" E.</p>
56.00	<p>Scattering timber, steep slope E.</p>
62.50	<p>Hill bears N.W. and S.E.</p>
76.25	<p>Foot of descent.</p>
76.65	<p>Branch of Buck Creek, 10 lks. wide, clear, pure water, runs N.30°W.</p>
76.75	<p>Scattered trail; ascend steep bank.</p>
80.00	<p>A point 700 ft. below the $\frac{1}{4}$ Sec. Cor. and the Cor. of Secs. 25 & 36, a Stone 16 x 12 x 4 ins., on W. hillside</p>