

## Township 3 N., R. 37 E., W.M.

Chains	Undergrowth: pine, fir, tamarack, alder, willow, pinegrass laurel, cherry, birch and bunchgrass. Good pasturage. Mountainous land- 52.50 chs.
	N.89° 44' W., on a true line; S. Bdy. of Sec. 35. Along steep, grassy S. slope.
4.00	Steeper descent into canyon of the S.Fork; bears N.W.& S.E.
10.50	Enter scattering timber and undergrowth.
19.75	Very steep descent; bears N.10°W and S.10°E.
22.50	Hill bears N.80°W and S.80° E.
30.00	Ascend steep hillside; bears N.80°E. and S.80:W.
37.00	Steep descent; bears N.20°W. and S.20°E.
40.00	A point 500 ft. below the Sec. Cor. and set a Basalt Stone, 20 x 8 x 4 ins., 15 ins. in the ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face and raise mound of stone 2 ft. base, $1\frac{1}{2}$ ft.high, N. of Cor. Pits impracticable. Find no trace of the old $\frac{1}{4}$ Sec. Cor. described by the Surveyor-General as a Stone, 18 x 8 x 7 ins. on S.W. hillside.
49.75	Enter timber and dense undergrowth; bears N.&S.
52.50	Down a steep, bluffy bank of river.
52.95	Seepage stream, 10 lks. wide, runs N.20°W., cross stony heavily timbered bar and bottom.
54.15	South Fork of Umatilla River, 15 lks. wide, pure water, flows N. 20°W., over stony bed. Strong current.
56.90	Trail- old, abandoned wagon-road; bears N.&.S.E.
57.75	Stock trail up right hand fork; bears N.70° E. and S.70°W
59.40	Right-hand fork, 75 lks. across, runs N.80° E. over stony, gravelly bottom.
61.00	Ascend steep, grassy hill; bears N.50°E and S.50°W.
65.75	Leave timber and cross lower end of open point-N.30°W
67.00	Enter heavy timber; bears N.30°W. and S.30°E.
70.00	Steep, grassy ascent thru scattering timber and undergrowth; bears N.70°E and S.70° W.
77.50	Ravine; course S.30°E.; steep ascent; bears N.10°E and S.