

Chains

58.50 Stock trail; bears N.W.& S.E.

60.00 Enter timber and dense undergrowth; bears N.W.& S.E.

60.50 Descend gradually

80.34 A point about level with the $\frac{1}{4}$ Sec. Cor. and the Cor. of T.3 N., Rs. 36 & 37 E., which is the stump of a fir, 36 ins. diam., (not a post as stated in the field notes furnished me), marked and witnessed as described by the Surveyor-General.

Land; nearly level and mountainous.

Soil: part arable, sandy loam, gravel and stone; 2nd and 3rd and 4th rates.

Heavily timbered with pine, fir, tamarack, spruce, alder and birch, 54.69 chs.

Densely overgrown with pine, fir, tamarack, spruce, alder willow, birch, cascara, elder, huckleberry, thimbleberry, pinegrass, fern, rosebriar and bunchgrass, 48.09 chains.

Mountainous, heavily timbered, on lands covered with dense undergrowth, 80.34 chs.

Good pasture land.

August 10, 1900.

Resurvey of the West Bdy. T.3 N., R.37 E., W.M.
As surveyed by Same Surveyor, under
Same Contract & Date.

Note: Failing to close random line between Secs. 30 and 31, as stated in field notes of survey of subdivisions, pg.48, I retrace W. Bdy. of Sec. 31 N., from S.W. Cor. of Township and at 40.00 chs. set temporary $\frac{1}{4}$ Sec. Cor.; at 40.64 chs. intersect the old $\frac{1}{4}$ Sec. Cor., as determined by the two witness trees described by the Surveyor-General, post missing; at 80.00 chs. set temporary Cor. of Secs. 30 & 31 and at 82.35 chs. fall 1 ch.25 lks. E. of the Cor. of Secs. 25 & 36. re-established by me, this day; therefore I resurvey W. Bdy. of Sec. 31 as follows:

From