

## Township 3 N., R. 37 E., W.M.

Chains	<p>stead of 1 ch., 46 lks. as stated in my copy of the original notes. I defer</p> <p>I defer obliterating marks on the S.E. witness tree until after closing of line between Secs. 22 &amp; 23.</p> <p>Thence I run</p> <p>S. 89° 34' E., on a true line, S. Bdy. of Sec. 14</p> <p>Descend along steep, stony side of canyon; bears N. 70° East and S. 70° West.</p> <p>4.00 Trail; bears N. 70° E. and S. 70° W.</p> <p>14.00 Foot; cross heavily timbered bottom.</p> <p>16.00 North Fork of the umatilla River, 30 lks. wide, flows S. 70° W. asce</p> <p>Ascend steep, bluffy base of mountain through timber and dense undergrowth; bears N.E. &amp; S.W.</p> <p>41.03 A point 100 ft. above the Sec. Cor. and the <math>\frac{1}{4}</math> Sec. Cor. S. Bdy. of Sec. 14,</p> <p>A fir post on N. face of bluff, marked and witnessed as described by the Surveyor-General.</p> <p>Thence I run</p> <p>N. 89° 54' E., on a true line S. Bdy. of Sec. 14.</p> <p>Thru partially deadened, windfallen timber and undergrowth.</p> <p>81.05 The closing Cor. of Secs. 23 and 24, now established, an ironstone, 10 x 5 x 5 ins., above the ground, marked and witnessed as described in the field notes of survey of subdivisions returned to the Surveyor-General.</p> <p>82.33 A point 100 ft. above the <math>\frac{1}{4}</math> Sec. Cor. and the Cor. of Secs. 13 and 14.</p>
	<p>Note:</p> <p>When 7 days later, the line between Secs. 22 and 23 was closed 1.13 chs. S. 89° 34' E. of the Cor. of Secs.</p>