

Township 3 N., R. 37 E., W.M.

Chains	<p>S.89° 45'W., on a blank line, S. Bdy. of Sec. 17; at 39.11 chs. set temp. $\frac{1}{4}$ Sec. Cor., N. Bdy. Sec. 20; at 40.83 chs., the old $\frac{1}{4}$ Sec. Cor., S. Bdy. of Sec.17, bears S.20 lks. 30 lks. dist.; at 80.75 chs. the Cor. of Secs. 17 & 18, a mound of stone, pits and stake, with marked stone, witnessed as described by the Surveyor-General, bears N.87lks. dist.</p>
	<p>Thence I run S.88° 34' E., on a true line, S. Bdy. of Sec. 17. Ascending thru dense undergrowth.</p>
1.72	<p>The closing Cor. of Secs. 19 & 20, as established later, a Basalt Stone, 10 x 5 x 5 ins. above ground, marked and witnessed as described in the field notes of survey of subdivisions, returned to the Surveyor-General. Thence leave undergrowth and ascend steep, stony Butte E. hill bears N.20°W. & S.20°E.</p>
6.72	<p>Stock trail; bears N.20°W. & S.20:E.</p>
15,50	<p>Top of bald Butte; descend into canyon of the Umatilla river, thru timber and undergrowth; irregular bearing N.W.& S.E.</p>
39.92	<p>The $\frac{1}{4}$ Sec. Cor., S. Bdy. of Sec. 17, a Basalt Stone, 28 x 14 x 7 ins., on E. side of Spur, as described by the Surveyor-General.</p>
	<p>Thence I run N. 89° ;9' E., on a true line, S. Bdy. of Sec.17.</p>
41.68	<p>A point 600 ft. below the Sec. Cor. and set a Basalt stone, 20 x 12 x 6 ins., 15 ins. in ground, for $\frac{1}{4}$ Sec. Cor., N. Bdy. Sec. 20, marked $\frac{1}{4}$ on S. face, and raise a mound of stone, 2 ft. base, 1$\frac{1}{2}$ft. high, S. of Cor. Pits impracticable.</p>
80.75	<p>The Cor. of Secs. 16 & 17, whence the closing Cor. of Sec. 20 & 21, bears N.89° 45'E., 89 lks. dist., 200 ft. below the $\frac{1}{4}$ Sec. Cor. 20 & 21, bears N.89° 45' E., 89 lks. dist., 200 ft. below the $\frac{1}{4}$ Sec. Cor.</p>
	<p>Land; mountainous. Soil; stony; 4th rate.</p>