

Chains	<p>survey returned to the Surveyor-General.</p> <p>Thence I run</p> <p>S.89° 55' W., on a true line between Secs. 24 &amp; 25.</p> <p>Ascending over rolling, stony, grassy land thru widely scattering timber; hill bears N.30°W and S.30° E.</p> <p>10.00 Hill bears N.E. &amp; S.W.</p> <p>24.75 Ravine, course S.35° E., thence steep ascent.</p> <p>31.25 Ravine, course SE. Thence very steep ascent thru heavy timber and dense undergrowth; bears N.20° E. and S.20° West.</p> <p>40.22 A point 300 ft. above the Sec. Cor. and set a Basalt Stone 30 X 12 X 4 ins., 22<math>\frac{1}{2}</math> ins. in the ground, for <math>\frac{1}{4}</math> Sec. Cor., marked <math>\frac{1}{4}</math> on N. face, from which,</p> <p>A pine, 24 ins. diam., bears S.18° W., 25 lks. dist. marked <math>\frac{1}{4}</math> S.25, B.T.</p> <p>A tamarack, 16 ins. diam., bears N.26<math>\frac{1}{2}</math> °W., 44 lks. dist marked <math>\frac{1}{4}</math> S.24, B.T.</p> <p>50.00 Gradual ascent over arable bench land; bears N.20° E. and S.20° W.</p> <p>55.00 Ascend from bench; hill bears N. &amp; S.</p> <p>60.50 Leave timber and dense undergrowth; same bearing.</p> <p>65.50 Gradual ascent over bald summit of divide.</p> <p>66.69 Trail from Toll-road; bears, with ridge, N.E. &amp; S.W.</p> <p>68.50 Top of divide; descend.</p> <p>71.25 Steep descent through timber and dense undergrowth; bears N.E. &amp; S.W.</p> <p>76.25 Thence along steep slope northward.</p> <p>80.44 A point 200 ft. above the <math>\frac{1}{4}</math> Sec. Cor. and the Cor. of Secs. 23, 24, 25 and 26.</p> <p>Land; gently sloping and mountainous.</p> <p>Soil; part arable; gravelly loam, sand and stone; 2nd, 3rd and 4th rates.</p> <p>Heavily timbered with pine, fir and tamarack, 29.25 chs.</p> <p>Undergrowth, pine, fir, tamarack, alder, maple, huckleberry, thimbleberry, rosebriar, and bunchgrasses.</p> <p>Good pasturage.</p>
--------	--