

Township 3 N., R. 37 E., W.M.

Chains

South Bdy. of Sec. 14, 1 ch. 28 lks. S. 89 ° 54' W. of the
the Cor. of Secs. 13 & 14, which is a Basalt Stone,
18 x 14 x 4 ins., marked as described by the Surveyor-
General and witnessed by the stump of the N. W. witness
tree,

A fir, 6 ins. diam., bearing N. 72° W., 55 lks. dist.,
marked T 3 N., R. 37 E., S. 14, B. T.

The other witness trees have been destroyed by fire and
no trees are left in limits to mark. Therefore, after
the retracement of S. Bdy. of Sec. 14, as detailed in
notes of resurvey, at the point intersection I set
an ironstone, 15 x 10 x 5 ins., 10 ins. in the ground
for closing of Cor. of Secs. 23 & 24, marked CC on S.
face, with 1 groove on E. and 5 grooves on W. faces,
from which,

The N. face of a ledge bears S. 42 ° E., 10 lks. dist
marked S. 24, B. O.

The N. face of a ledge bears S. 15½ ° W., 9½ lks. "
marked S. 23, B. O.

The ground is too steep for mound of stones and pits are
also impracticable.

Land; mountainous.

Soil; gravelly and stony; 3rd and 4th rates.

Timber; pine, fir and tamarack.

Undergrowth; pine, fir, tamarack, alder, maple, willow,

huckleberry, thimbleberry, elder, fern and bunchgrasses

Good pasture land.

Mountainous land, 76.60 chs.

Overcast at 12 M; observation for lat. not possible.

August 1, 1900.

On the S. Bdy. of the Tp., established by me this day;
viz; a Basalt Stone, 20 x 15 x 8 ins. set firmly in
the ground, with mound of stones about Cor., marked
and witnessed as described in the field notes of re-
survey returned to the Surveyor- General.

Thence I run