

Chains	
	N. 0° 1' W., between Secs. 34 & 35. Slightly ascending over main ridge between the S.Fork of Umatilla River and Buck Creek through scattering timber and undergrowth.
1.03	Stock trail along ridge; bears N.70° W. and S.70° E.
4.25	Top of divide and descend.
5.25	Steeper descent of mountain; bears N.80° W. and S.80° E
6.00	Enter dense undergrowth.
8.25	Enter heavy timber.
15.00	Hill bears N.W.& S.E.
22.00	Cross ridge-point N.10° E.
24.00	Hill bears N.70° E. and S.30° W.
27.00	Ravine, course N.30° E., thence hill bears N.20° W. and S.20° E.
37.60	Rill, 1 lk. wide, runs N.60° E., thence irregular slope N.75° E.
40.00	A point 1100 ft. below the Sec. Cor. and A fir, 6 ins. diam., for $\frac{1}{4}$ Sec. Cor., I mark $\frac{1}{4}$ S. on W. side, from which A fir, 6 ins. diam., bears N.7° E., 27 lks. dist. marked $\frac{1}{4}$ S. 35,B.T. A fir, 30 ins. diam., bears S.10°W., 40 lks. dist. marked $\frac{1}{4}$ S. 34,B.T.
45.75	Leave timber and undergrowth; bears N.30° E. & S.30° W.; steep, grassy slope N.80° E.
54.00	Steep descent through timber and dense underhrowth;bears N.80° W. and S.80° E.
62.00	Rill, 1 lk. wide, runs N.65° E., ascend; hill bears N.30° E. and S.30° W.
66.50	Leave timber and undergrowth.
80.00	A point 100 ft. above the $\frac{1}{4}$ Sec. Cor. and a rock in place 8 x 6 x 4 ins. above ground, for Cor. of Secs. 26, 27, 34 & 35, on which I Cut a cross (X) at the exact Cor. point, marked with one notch on S. and 2 notches on E. edges, from which A fir, 10 ins. diam., bears N.25 $\frac{1}{2}$ ° E., 1 ch.25 lks.