

Township 3 N., R.37 E., W.M.

Chains	
	N.0° 2' W., between Secs. 33 & 34. Ascending over stony, grassy ridge.
3.25	Top of ridge-point, W.; descend; hill bears N.60° E. and S.60° W.
4.25	Enter dense undergrowth.
4.75	Enter small sized timber; bears E. & W.
10.00	Bottom of deep, wooded ravine, course S.60° W.; ascend.
11.00	over bare, grassy point.
15.00	Top of point, course W.; descend.
15.75	Enter dense undergrowth; bears E.&W.
17.25	Bottom of Ravine, course S.60° W., ascend.
17.75	Leave undergrowth
24.25	Top of point, course W.; stony descent; bears N.30° E. and S.30° W.
25.50	Enter small timber and dense undergrowth.
30.00	Scattering timber and undergrowth; steep slope N.80° W.
33.25	Enter small timber; steeper descent; bears N.75° E. and S.75° W.
40.00	A point 200 ft. below the Sec. Cor. and set a trapstone 24 x 10 x 3 ins., 18 ins. in the ground, for $\frac{1}{4}$ Sec. marked $\frac{1}{4}$ on W. face, from which, A tamarack, 18 ins. diam., bears N.69° E., 33 lks. dist., marked $\frac{1}{4}$ S. 34, B.T. A fir, 42 ins. diam., bears W. 5 $\frac{1}{2}$ lks. dist., marked $\frac{1}{4}$ S. 33, B.T.
45.50	Foot; rill, 1 lk. wide, runs N.80° W.; thence steep ascent; bears N.70° W. and S.70° E.
47.00	Scattering timber and undergrowth.
56.35	Thicker growth of timber.
57.00	Top of point-W.; steep descent; bears E.&W.
63.15	Foot; dry bed of stream, 3 lks. wide; course N.80° W.; ascend steep, grassy hill; bears N.W. & S.E.
64.50	Widely scattering timber and undergrowth.
72.00	Steep slope westward.
77.70	Ravine, course S.W.; ascend steep, grassy hill through dense undergrowth; bears E.&W.