

Township 3 N., R.37 E., W.M.

Chains	<p>marked T.3 N., R.37 E., S.22, B.T.</p> <p>A fir, 20 ins.diam., bears S.21$\frac{3}{4}$°E., 1ch.90lks.dist.</p> <p>marked T.3 N., R.37 E.,S.27, B.T.</p> <p>A fir, 14 ins. diam., bears N.60$\frac{1}{2}$° W., 99 lks.dist., marked T.3 N., R.37 E.,S.21, B.T.</p> <p>Land; mountainous and gently sloping.</p> <p>Soil: sandy, gravelly and stony;2nd,3rd and 4th rates.</p> <p>Heavily timbered with pine, fir, tamarack and cottonwood 10.00 chs.</p> <p>Densely overgrown with pine, fir, tamarack, alder,willow ninebark, rosebriar, huckleberry,service and thimble- berry, fern and bunchgrasses, 15.50 chs.</p> <p>Good pasturage.</p> <p>Mountainous, heavily timbered or densely overgrown,78 chs</p>
40.00	S.89° 43' E. on a random line between Secs. 22 and 27. Set temp. $\frac{1}{4}$ Sec. Cor.
80.46	Intersect N.&S.line, 7 lks. N. of the Cor. of Secs. 22, 23,26 & 27. Thence I run N.89° 40' W., on a true line between Secs, 22 & 27. Descending stony, grassy hillside; bears N.80° W. and S.80° E.
3.00	Stock trail; bears N.E. and S.W.
4.50	Enter timber; bears N.&S.
7.90	Same trail; bears N.&S.
12.50	Steeper descent; bears N.E. and S.W.
15.75	Stock trail; bears N.&S.
16.50	Along steep side of Ravine; slope N.20° W.
25.25	Foot; Ravine;S.20° W.; ascend over stony point thru scattering timber and undergrowth.
31.50	Top of point; stock trail; bears N.&S.; descend stony, grassy hillside; bears N.70° W. and S. 70° E.
40.23	A point 650 ft. below the Sec. Cor. and set a Basalt Stone, 15 x 10 x 5 ins., 10 ins. in the ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face, from which, A pine, 14 ins. diam., bears N.31 $\frac{1}{4}$ ° E., 1 ch. 60 lks.