

Chains	
	Dist. dist., marked $\frac{1}{4}$ S.22, B.T. A pine, 16 ins. diam., bears S.25° W., 1 ch. 95 lks. dist., marked $\frac{1}{4}$ S.27, B.T.
44.50	Ravine; course S.15° W., more gradual descent through partially burnt timber.
50.50	Foot; cross stony bottom through heavy timber.
52.00	Trail along stream; bears ^{N.} 60° W. and S.60° E.
53.80	Buck Creek, 20 lks. wide, runs N.W.
54.25	Leave bottom and ascend steep point through scattering partially burnt timber and dense undergrowth; bears N.75° W. and S.75° E.
63.68	Trail to Buck Mt.; bears N.W. & S.E., steep descent to ridge-point-N.W.; bears N.10° E. and S.10° W.
67.00	Enter heavy timber.
71.00	Old Indian trail to grazing grounds; bears N. & S.E.
73.50	Down bluff bank of river.
74.00	Foot; leave dense undergrowth and cross stony bottom.
75.00	South Fork of Umatilla River, 40 lks. wide, runs N.10° W.
77.96	Old "Thomas and Burkell" stage road to Boise; bears N.20° E. and S.20° W.
78.28	Ascend steep, bluff bank.
80.46	A point about level with the $\frac{1}{4}$ Sec. Cor. and the Cor. of Secs. 21, 22, 27 & 28. Land; level, rolling and mountainous. Soil; small part arable; sandy loam, gravel and stone; 2nd, 3rd and 4th rates. Heavily timbered with pine, fir, tamarack and cottonwood 37.96 chs. Densely overgrown with pine, fir, tamarack, alder, willow, ninebark, thimbleberry, elder, fern, pinegrass, rosebriar and bunchgrass, 19.75 chs. Good pasturage. Mountainous, heavily timbered, or densely overgrown land, 80.46 chs.

August, 15, 1900

Thence I run

N.0°2' W., between Secs. 21 and 22.