

Township 3 N., R.37 E., W.M.

Chains
 erous growth of bunch and other nutritious grasses; affording a bountiful range for stock during most of the year.
 Pine, fir and tamarack timber abounds throughout most sections; cottonwood, alder and a better quality of pine along the streams.
 The township is well watered by the Umatilla River and its branches and by many small springs of pure water. There is one settler at present in Sec. 21 and two in Sec. 22.

Wm. E. Campbell,

U.S. Deputy Surveyor.

Retracement of East Bdy. T 3 N., R.37 E., W.M.
 Surveyed by John W. Kimbrell, Deputy Surveyor
 Under Contract No. 700, dated Feb. 9, 1899.
 Survey began June 25, 1903
 Survey completed Sept. 7, 1903.

Determined a true meridian with the solar at the Cor. of Secs. 25 and 36 on the E. Bdy. of T.3 N., R.37 E.
 Thence I run,
 North on E. Bdy. of Sec. 25,
 40.00 A Stone marked and witnessed, bears E. 36 lks. dist. of this Cor. I have no account; the old Sec. Cor., a stone with bearing trees destroyed) as described by the Surveyor-General, bears S 1° W., 128 lks. dist.
 The true course of this line is N. 31° E., 40.00 chs.
 Thence N. 31° E.
 40.05 A point 2 lks. W. of Cor. of Secs. 24 & 25, which is a stone marked and witnessed, from which, the old Sec. Cor. as described by the Surveyor-General, also destroyed, bears S. 3½° E. 255 lks. dist.
 True course of this line is N. 33° E. 40.05 chs.
 Land; mountainous.
 Soil; rocky, poor 4th rate.
 Timber; fir, spruce and pine.
 Dense undergrowth; alder and willow.
 Mountainous land, 80.05 chs.